



County of Lake, Ohio

**OFFICE OF THE
COUNTY ENGINEER**

April 17, 2013

FOR COUNTY PROJECT NO. 05-026-01

VROOMAN ROAD – STATE ROUTE 86 – ROUNDABOUT

ADDENDUM NO. 1

The following is Addendum No. 1 to the bid documents for: Vrooman Road – S.R. 86 – Roundabout.

1. Maintenance of Traffic Notification Requirement – The Contractor shall notify all local businesses, fire and safety, Township and others as directed by the County Engineer's office approximately one week before the initial road closure and before beginning a new detour phase. Contact list will be provided in the preconstruction meeting.
2. The attached Utilities 4A Note shall be included and made part of the bid documents. All utility coordination as required shall be included in Item 624 – Mobilization (Reference #71).
3. Item 619 – Field Office, Type "B" (Reference #69) shall have the estimated quantity revised from 18 months to 8 months.
4. Item 452 – 8" Non-Reinforced Concrete Pavement, As Per Plan (Reference #32) shall have a brick stamp pattern with the appearance as shown on sheet 2 of 76 in the plans. The coloring shall provide a "red brick" paver appearance. A mockup of the stamped and colored concrete shall be provided to the County for approval.
5. Item 304 – Aggregate Base, As Per Plan (Reference #21) shall be per specification Item 3.B. Crushed concrete meeting the specified gradation is acceptable.
6. Replace field access drive and curb cut at Station 103+98 to Station 104+16 LEFT.



County of Lake, Ohio

OFFICE OF THE
COUNTY ENGINEER

April 17, 2013

FOR COUNTY PROJECT NO. 05-026-01

VROOMAN ROAD – STATE ROUTE 86 – ROUNDABOUT

7. Add 12" Conduit, Type "B"
Left swale line: Sta. 103+93, invert = 946.00 to Sta. 104+21, invert = 945.90
Item 603 – 12" Conduit, Type "B" (Reference #44) shall be revised from 172 Ft. to 202 Ft.
8. Revise CB 2-3 Sta. 105+50 Lt. from grate elevation 946.58 to elevation 945.48.
9. Item 832 – Erosion Control (Reference #122) shall be revised from 45,000 to 20,000 EACH.
10. The attached Revised Proposal shall replace the proposal that is currently in the bid documents.

This addendum shall be attached to the proposal and become part of the bidding document to verify receipt of same.

Utilities 4A Note

Bidders are advised that the following utility facilities are in the project area. These utility facilities shall be relocated within the construction limits of the project as set out below.

Orwell-Trumbull, Cobra Pipeline

The company has existing facilities in the area of the project that will need to be relocated. The county is coordinating with Orwell-Trumbull/Cobra Pipeline. No schedule is available at this time.

The Illuminating Company

The company has existing facilities in the project area. The power lines in the area will require permanent pole adjustments in order to avoid conflicts with proposed plan. The relocation plans have been received and approved. They have pre-construction activities planned for May, 2013 (see the attached Illuminating Company letter). Contractor shall give The Illuminating Company 2 weeks notice prior to the end of the project such that they can schedule their post construction activities accordingly.

AT&T Ohio

The company has aerial and underground facilities within the project area. They have been contacted. No plans for relocation have been submitted to date.

Time Warner Cable

The company has aerial facilities within the project limits. This facility will require detachment from the existing poles and re-attachment to the new poles. The county and The Illuminating Company will coordinate the demolition procedures with Time Warner Cable.

The Contractor shall use extreme caution when working in proximity to existing utility facilities.

Sections 105.07 and 107.16 of the Ohio Department of Transportation Construction and Material Specifications require, among other things, that the contractor cooperate with all utilities located within the limits of this construction project and take responsibility for the protection of the utility property and services.



Northern Region Engineering Services
Project Response for LAK Vrooman Rd Roundabout
Reference Illuminating Company File – WR # WR 55835526

April 12, 2013

Lake County Engineer
550 Blackbrook Rd.
Painesville, Ohio 44077

Attention: Erin M. Fink P.E.

The following information indicates the Illuminating Company's findings after examining the information previously received by the Illuminating Company on 10/15/2012 for the aforementioned project.

- 1. The Illuminating Company has no facilities in conflict on this project.
- 2. Rearrangement of the Illuminating Company's facilities is not necessary.
- 3. **The Illuminating Company has facilities in conflict and will be required to rearrange them.**
- 4. Based upon plans or information received, it is indeterminate if rearrangement of our facilities is necessary. Please provide the additional information requested below.

Prior to the Illuminating Company commencing work on aerial or underground facilities in support of roadway, sanitary, storm or water line projects, all clearing, grubbing, necessary forestry (tree/bush trimming) in the Public Right of way is to be completed by others. Final grade shall be established prior to the Illuminating Company installing or relocating underground electric distribution facilities. Also, the project construction limits are to be surveyed and staked by the requesting engineering consulting firm or by the municipality in order ensure the Illuminating Company is properly locating aerial facilities in the public right of way and within the construction limits.

Relocation costs that are determined to be compensable, such as, sanitary sewer projects, water lines and other compensable rights or where the relocation of our overhead facilities is only caused by the installation of sidewalks, shall be invoiced by the Illuminating Company per our standard Aid to Construction form. Payment shall be received in advance of work commencing. Estimates are only valid for 30 days and will be re-estimated to provide current estimated costs should approvals be extended beyond the 30 days.

In the event additional conflicts are identified which are not part of the Project 4A Note/Project Response Form, due to field conditions, the Illuminating Company shall be notified immediately, both verbally and in writing by the authorized agent for the project. The Illuminating Company, along with the contractor and authorized agent for the project, shall resolve the field conflicts and determine if there are associated compensable costs. The Illuminating Company will not accept contractor delay costs that the Company has not had opportunity to dispute or resolve.

Important! Illuminating Company High-Voltage Transmission lines can not readily or easily be de-energized. They operate under strict Federally-Mandated oversight. De-energizing is a lengthy, costly process, and all other options must be exhausted prior to considering de-energizing High-Voltage Transmission lines. Permission to de-energize may be withheld depending on many factors, including but not limited to: ambient temperature, customer load, possible weather events, and many other contingencies. Further, if de-energizing is ultimately allowed, the High-Voltage Transmission lines must remain in a condition that they can be "restored" to service in an emergency. Therefore, any personnel, tools, equipment and all appurtenances must be

in a position and condition to move/reposition (within two-hours of notice) into a safe, OSHA-acceptable distance from the High-Voltage Transmission lines, and the High-Voltage Transmission lines must be considered as energized while steps are taken to re-energize the High-Voltage Transmission lines. Payment shall be received in advance of work commencing. Estimates are only valid for 30 days and will be re-estimated to provide current estimated costs should approvals be extended beyond the 30 days.

I. WOOD-POLE AERIAL DISTRIBUTION FACILITIES

The Illuminating Company's wood pole facilities will be rearranged according to the attached WR 55835526.pdf. Associated CEI work has pre and post construction activities.

Pre-construction Activities include but not limited to:

Symbol #2 Pole 553444 at STA 302 +08 31'RT to be substituted to a larger pole in place. Pole is to be set deeper.
Symbol #6 Pole 553415 pole to be removed at STA 206+26 09' LT Telephone to remove pole.
Symbol #8 Pole 556227 pole to be relocated from STA 105+99 RT to 105+50 27'RT Telephone to remove pole.
Symbol #9 Pole 556229 pole to be removed. Telephone to remove pole.
Symbol #10 Pole 556230 pole to be relocated from STA 102+98 26' RT to STA 103+48 24'RT Telephone to remove pole.
Wire work as noted on WR 55835526.pdf Wire Work Before Road Construction Begins.

Post Construction Activities include but not limited to:

Symbol #7 New Pole 735726 to be set at STA 107+07 08'LT.
Symbol #11 Pole 278938 pole to be relocated from STA 207+47 46'RT to STA 207+80 40'RT Telephone to remove pole.
Wire work as noted on WR 55835526.pdf: Wire Work After Road Construction Has Been Completed.

Work Week:

The Illuminating Company's workweek is comprised of 5 days per week, 8 hours per day, Monday through Friday. Any overtime costs incurred, as a result of contractor project escalation or requests from ODOT, Cuyahoga County or other project administering agencies shall be billed directly to the contractor. Authorization for payment for the requested overtime shall be received in advance of the overtime being worked.

Additional Comments:

For the purposes of 29 CFR 1926 Subpart CC, the electric distribution facilities proximate to the structure are energized at less than 50,000-Volts All contractors/owners must know & comply with Occupational Safety Health Administration (OSHA) safe-working clearances between persons or any conductive object and energized bare wires.

Notice: The Illuminating Company denies permission to any contractor or other utility to remove Illuminating Company manhole castings, cut down Illuminating Company manhole necks, and to temporarily plate over project-created Illuminating Company manhole roof openings. This practice often results in construction debris falling into manholes, thus damaging energized circuits. Under any circumstances if project construction debris is found in Illuminating Company manholes on the subject project, the Illuminating Company shall charge the responsible party for the required clean out. In the event circuitry is damaged as a direct result of project construction debris, the Illuminating Company shall also file a claim, and pursue reimbursement for the damage. It is the Project General Contractor responsibility to notify the Illuminating Company in advance of any existing debris found in Illuminating Company manholes.

Notice: Customer-owned secondary cables/wire and equipment that requires relocation caused by a public works project is not the responsibility of The Illuminating Company. The relocation cost for customer owned facilities generally is the responsibility of the requesting agency.

Notice: In the event of a major storm in our service territory, the Illuminating Company's priority becomes the safety of the general public and employees. Efforts are directed to the safe and timely restoration of electrical service to our customers which may affect the projects overall schedule.

The Illuminating Company

Mark Robinson
Project Manager
Northern Region Operations

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

1. The undersigned BIDDER proposes and agrees, if this Bid is accepted, to enter into an Agreement with OWNER in the form included in the Contract Documents to perform and furnish all work as specified or indicated in the Contract Documents for the amount Bid and within the time indicated in this Bid and in accordance with the other terms and conditions of the Contract Documents.
2. In submitting this Bid, BIDDER represents, as more fully set forth in the Agreement, that:

- a. BIDDER has examined copies of all the Bidding Documents and of the following Addenda (receipt of all which is hereby acknowledged):

<u>Date</u>	<u>Number</u>
_____	_____
_____	_____
_____	_____

- b. BIDDER has visited the site and become familiar with and is satisfied as to the general, local, and site conditions that may affect cost, progress, performance, and furnishing of the work.
- c. BIDDER is familiar with and is satisfied as to all federal, state, and local LAWS and Regulations that may affect cost, progress, performance, and furnishing of the work.
- d. BIDDER is aware of the general nature of work to be performed by OWNER and others at the site that relates to work for which this Bid is submitted as indicated in the Contract Documents.
- e. BIDDER has correlated the information known to BIDDER, information and observations obtained from visits to the site, reports and drawings identified in the Contract Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Contract Documents.
- f. BIDDER has given ENGINEER/ARCHITECT written notice of all conflicts, errors, ambiguities, discrepancies that BIDDER has discovered in the Contract Documents and the written resolution thereof by ENGINEER/ARCHITECT is acceptable to BIDDER, and the Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the work for which the Bid is submitted.
- g. This Bid is genuine and not made in the interest or on behalf of any undisclosed person, firm, or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization, or corporation; BIDDER has not directly or indirectly induced or solicited any other BIDDER to submit a false or sham Bid; BIDDER has not solicited or induced any person, firm, or corporation to refrain from bidding; and BIDDER has not sought by collusion to obtain for itself any advantage over any other BIDDER or over OWNER.
- h. *All bidders are required to attend a MANDATORY Pre-Bid Conference on **Monday, April 15, 2013, 10:00 a.m.**, at the Lake County Engineer's Office, 550 Blackbrook Road, Painesville, OH 44077. Failure to attend the Pre-Bid Conference will subject the bidder's proposal to be considered non-responsive.*

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
1.	103	Premium for Contract, Performance, Payment and Maintenance Bond	1	Lump	\$	\$
2.	201	Clearing and Grubbing, Brush	1	Lump	\$	\$
3.	202	Headwall Removed	4	Each	\$	\$
4.	202	Pavement Removed, Asphalt	7,649	S.Y.	\$	\$
5.	202	Pipe Removed, 24" and Under	311	Ft.	\$	\$
6.	202	Pipe Removed, Over 24"	212	Ft.	\$	\$
7.	202	Mailbox Removed	9	Each	\$	\$
8.	202	Fence Removed	158	Ft.	\$	\$
9.	202	Catch Basin Removed	1	Each	\$	\$
10.	202	Removal Misc., Flower Bed Removed	4	Each	\$	\$
11.	202	Removal Misc., Brick Wall Removed	103	Ft.	\$	\$
12.	203	Excavation	2,065	Cu. Yd.	\$	\$
13.	203	Embankment	5,163	Cu. Yd.	\$	\$
14.	204	Subgrade Compaction	11,131	Sq. Yd.	\$	\$
15.	204	Excavation of Subgrade	3,000	Cu. Yd.	\$	\$
16.	204	Granular Material, Type "B"	3,000	Cu. Yd.	\$	\$
17.	204	Proof Rolling	5.0	Hours	\$	\$
18.	204	Geotextile Fabric	4,700	Sq. Yd.	\$	\$
19.	301	Asphalt Concrete Base, PG64-22	1,128	Cu. Yd.	\$	\$
20.	301	Asphalt Concrete Base, PG64-22, Driveways	131	Cu. Yd.	\$	\$
21.	304	Aggregate Base, As Per Plan	1,751	Cu. Yd.	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
22.	407	Tack Coat	586	Gal.	\$	\$
23.	407	Tack Coat for Intermediate Course	271	Gal.	\$	\$
24.	410	Traffic Compacted Surface, Type "A" or "B"	458	Cu. Yd.	\$	\$
25.	410	Traffic Compacted Surface, Type "C"	229	Cu. Yd.	\$	\$
26.	411	Stabilized Crushed Aggregate	13	Cu. Yd.	\$	\$
27.	448	Asphalt Concrete Intermediate Course, Type "2", PG64-22	235	Cu. Yd.	\$	\$
28.	448	Asphalt Concrete Surface Course, Type "1", PG70-22M, As per Plan	329	Cu. Yd.	\$	\$
29.	448	Asphalt Concrete Surface Course, Type "1", PG64-22, Driveways	35	Cu. Yd.	\$	\$
30.	452	4" Non-Reinforced Concrete Pavement	616	Sq. Yd.	\$	\$
31.	452	6" Non-Reinforced Concrete Pavement	67	Sq. Yd.	\$	\$
32.	452	8" Non-Reinforced Concrete Pavement, As per Plan	411	Sq. Yd.	\$	\$
33.	601	Rock Channel Protection, Type "B", with Filter	2	Cu. Yd.	\$	\$
34.	601	Rock Channel Protection, Type "C", with Filter	54	Cu. Yd.	\$	\$
35.	602	Concrete Masonry	2.4	Cu. Yd.	\$	\$
36.	603	4" Conduit, Type "B"	100	Ft.	\$	\$
37.	603	4" Conduit, Type "C"	100	Ft.	\$	\$
38.	603	4" Conduit, Type "E"	300	Ft.	\$	\$
39.	603	4" Conduit, Type "F"	100	Ft.	\$	\$
40.	603	6" Conduit, Type "F", for Underdrain Outlets	250	Ft.	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
41.	603	6" Conduit, Type "B"	134	Ft.	\$	\$
42.	603	6" Conduit, Type "E"	100	Ft.	\$	\$
43.	603	6" Conduit, Type "F"	100	Ft.	\$	\$
44.	603	12" Conduit, Type "B"	202	Ft.	\$	\$
45.	603	12" Conduit, Type "C"	452	Ft.	\$	\$
46.	603	12" Conduit, Type "D"	20	Ft.	\$	\$
47.	603	30" Conduit, Type "B"	78	Ft.	\$	\$
48.	603	30" Conduit, Type "C"	444	Ft.	\$	\$
49.	603	22"x34" Conduit, Type "A", 706.04	70	Ft.	\$	\$
50.	604	Catch Basin, No. 3	4	Each	\$	\$
51.	604	Catch Basin, No. 3A	8	Each	\$	\$
52.	604	Catch Basin, No. 2-2B	1	Each	\$	\$
53.	604	Catch Basin, No. 2-3	2	Each	\$	\$
54.	604	Manhole, No. 3	3	Each	\$	\$
55.	604	Special – Misc. Metal	1,000	Lb.	\$	\$
56.	605	6" Base Pipe Underdrains	3,969	Ft.	\$	\$
57.	609	Combination Curb and Gutter, Type "2"	4,282	Ft.	\$	\$
58.	609	Combination Curb and Gutter, Type "3", As per Plan	309	Ft.	\$	\$
59.	609	Curb, Type "6"	494	Ft.	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
60.	609	Curb, Type "6", As per Plan	294	Ft.	\$	\$
61.	609	Curb, Type "7"	200	Ft.	\$	\$
62.	614	Maintaining Traffic	1	Lump	\$	\$
63.	614	Detour Signing	1	Lump	\$	\$
64.	614	Work Zone Edgeline, Class "1"	0.21	Mile	\$	\$
65.	614	Asphalt Concrete for Maintaining Traffic	1,100	Cu. Yd.	\$	\$
66.	614	Law Enforcement Officer with Patrol Car for Assistance	80	Hours	\$	\$
67.	615	Pavement for Maintaining Traffic, Class "A"	126	Sq. Yd.	\$	\$
68.	616	Water	44	MGal.	\$	\$
69.	619	Field Office, Type "B"	8	Month	\$	\$
70.	623	Construction Layout Stakes	1	Lump	\$	\$
71.	624	Mobilization	1	Lump	\$	\$
72.	625	Connection, Fused Pull Apart	18	Each	\$	\$
73.	625	Light Pole, Conventional, A10B30	9	Each	\$	\$
74.	625	Light Pole Foundation, 24" x 8' Deep	9	Each	\$	\$
75.	625	No. 8 AWG 600 Volt Distribution Cable	5,487	Ft.	\$	\$
76.	625	No. 10 AWG Pole and Bracket Cable	810	Ft.	\$	\$
77.	625	Conduit, 2", 725.05	1,142	Ft.	\$	\$
78.	625	Conduit, 3", 725.04	205	Ft.	\$	\$
79.	625	Luminaire, Conventional Type "II", 250W HPS, 240 Volt	9	Each	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
80.	625	Glare Shield	5	Each	\$	\$
81.	625	Trench	1,347	Ft.	\$	\$
82.	625	Pull Box, 725.08, 18"	10	Each	\$	\$
83.	625	Ground Rod	9	Each	\$	\$
84.	625	Power Service, As per Plan	1	Each	\$	\$
85.	625	Plastic Caution Tape	1,347	Ft.	\$	\$
86.	625	Special – Maintain Existing Lighting	1	Lump	\$	\$
87.	625	Luminaire Removed	3	Each	\$	\$
88.	625	Disconnect Circuit, As per Plan	3	Each	\$	\$
89.	625	Lighting Misc. – Weatherproof Receptacle	1	Each	\$	\$
90.	630	Ground Mounted Support, No. 2 Post	114	Ft.	\$	\$
91.	630	Ground Mounted Support, No. 3 Post	644	Ft.	\$	\$
92.	630	Ground Mounted Support, No. W10x12 Beam	114	Ft.	\$	\$
93.	630	Sign Post Reflector	49	Each	\$	\$
94.	630	Breakaway Beam Connection	8	Each	\$	\$
95.	630	Sign Erected, Flat Sheet	447	Sq. Ft.	\$	\$
96.	630	Sign Erected, Extrusheet	170	Sq. Ft.	\$	\$
97.	630	Ground Mounted Beam Support Foundation	8	Each	\$	\$
98.	630	Removal of Ground Mounted Sign and Disposal	26	Each	\$	\$
99.	630	Removal of Ground Mounted Sign and ReErection	6	Each	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
100.	630	Removal of Ground Mounted Post Support and Disposal	18	Each	\$	\$
101.	630	Removal of Pole Mounted Sign and Disposal	4	Each	\$	\$
102.	644	Edge Line	0.25	Mile	\$	\$
103.	644	Center Line	0.51	Mile	\$	\$
104.	644	Stop Line	18	Ft.	\$	\$
105.	644	Transverse/Diagonal Line	220	Ft.	\$	\$
106.	644	Yield Line	72	Ft.	\$	\$
107.	644	Dotted Line, 8"	153	Ft.	\$	\$
108.	659	Soil Analysis Test	2	Each	\$	\$
109.	659	Topsoil	990	Cu. Yd.	\$	\$
110.	659	Seeding and Mulching	8,770	Sq. Yd.	\$	\$
111.	659	Repair Seeding and Mulching	446	Sq. Yd.	\$	\$
112.	659	Inter - Seeding	446	Sq. Yd.	\$	\$
113.	659	Commercial Fertilizer	1.2	Ton	\$	\$
114.	659	Lime	1.9	Acres	\$	\$
115.	659	Water	24	MGal.	\$	\$
116.	670	Ditch Erosion Protection	185	Sq. Yd.	\$	\$
117.	690	Special – Mailbox Support System, Single	9	Each	\$	\$
118.	690	Special – Work Involving Petroleum Contaminated Soil	20	Ton	\$	\$
119.	690	Special – Work Involving Water	200	Gal.	\$	\$
120.	690	Special – Work Involving Regulated Water	100	Gal.	\$	\$

REVISED PROPOSAL SHEET FOR ADDENDUM 1

Vrooman Road – State Route 86 Roundabout
Leroy Township, Ohio

LCE Project No. 05-026-02

Ref. No.	Item	Description	Estimated Quantity	Measure Unit	Unit Price Bid	Total Bid
121.	832	Stormwater Pollution Prevention Plan	1	Lump	\$	\$
122.	832	Erosion Control	20,000	Each	\$1.00	\$20,000.00
123.	835	Exfiltration Trench, Type "A"	92	Ft.	\$	\$
124.	836	Seeding and Erosion Control with Turf Reinforced Mat, Type "1"	484	Sq. Yd.	\$	\$
125.	836	Seeding and Erosion Control with Turf Reinforced Mat, Type "2"	42	Sq. Yd.	\$	\$
		GRAND TOTAL				\$

3. BIDDER will complete the work for the following price(s):

BIDDER agrees to perform all the work described in the Contract Document for the prices shown on the following Base Bid Proposal Sheets combined for the Grand Total indicated below, in written and numeric form:

(\$ _____)

The BIDDER agrees to furnish all services, labor, material and equipment necessary to complete the job per the Scope of Services. The BIDDER agrees that the work will be complete and ready for final payment by **Friday, November 15, 2013.**

SUBMITTED BY: _____ SIGNED BY: _____

ADDRESS: _____ TITLE: _____

_____ PHONE NO.: _____

FAX NO.: _____