

Project Location

The Vrooman Road/SR 86 Roundabout is located in Leroy Township where Vrooman Road, SR 86, Leroy Center Road and Huntoon Road intersect. The area is referred to by locals as "5 Points."

Project Description

The project entails the construction of a roundabout at the intersection of Vrooman Road, SR 86 and Leroy Center Road and the realignment of the SR 86 and Huntoon Road intersection. The project includes approach work, paving, signing, pavement markings, drainage, lighting, and restoration.

Contractor

JTO, Inc of Mentor, Ohio is hired as the contractor for the \$1.4 million dollar project.

Project Schedule

The roundabout is scheduled to be constructed in four (4) phases and will be complete by November 15, 2013. The schedule is flexible and may be adjusted due to weather delays and/or to lessen the impacts to the traveling public. Each phase is expected to last 30 days.

- **Phase 1 – Close Leroy Center Road.** Leroy Center traffic will be detoured via SR 86 and Brakeman Road. Traffic will be maintained on Vrooman Road, SR 86 and Huntoon Road.

Work will include the construction of the easterly portion of the roundabout including splitter island, curb and gutters, and drainage.

- **Phase 2 – Close Vrooman and Leroy Center Roads.** Leroy Center Road will remain closed and traffic will continue to be detoured via SR 86 and Brakeman Road. Vrooman Road traffic will be detoured via SR 86 and Carter Road. Trucks may desire to use SR 86, SR 84, and SR 44 to access I-90 for ease of travel. Traffic will be maintained on SR 86. Work will include construction of the northern portion of the roundabout pavement including splitter island, curb and gutter, and drainage. Local access to properties shall be maintained at all times.

VROOMAN ROAD ROUNDABOUT CONSTRUCTION PROJECT

STATE/OPWC Project No.: CG04P & CG05P

Lake County Project No.: 05-026-02

Location:	Vrooman Road Southern extent intersection with State Route 86 in Leroy Township.
Description:	The proposed project will construct a roundabout improvement at the intersection of State Route 86, Vrooman Road and Leroy Center Road. Huntoon Road will be realigned to the north leg of State Route 86. Construction will include signage, lighting and drainage improvements.
Schedule:	Start: June 2013 End: November 2013
Detour:	Varies. Visit the Lake County Engineer's website for updates.
Contractor:	JTO, Inc.
Lake County Contact:	Traci Salkiewicz, P.E. 440.350.2770 ext. 239 Traci.Salkiewicz@lakecountyohio.gov

- **Phase 3 – Close SR 86 south of the Roundabout and Huntoon Road.** SR 86 south of the roundabout and Huntoon Road will be closed. SR 86 traffic will be detoured via US 6, SR 44 and SR 84. Huntoon Road traffic will be detoured via Williams Road and SR 86. Vrooman Road, Leroy Center Road and the north leg of SR 86 will be open to traffic.

Work will include construction of the southeasterly portion of the roundabout pavement including splitter island, curb and gutter, and drainage. Local access to properties shall be maintained at all times.

- **Phase 4 – Close SR 86 north of the Roundabout and Huntoon Road.** SR 86 north of the roundabout and Huntoon Road will be closed. SR 86 traffic will be detoured via US 6, SR 44 and SR 84. Huntoon Road traffic will be detoured via Williams Road and SR 86. Vrooman Road, Leroy Center Road and the north leg of SR 86 will be open to traffic.

Work will include construction of the northwesterly portion of the roundabout pavement including splitter island, curb and gutter, and drainage. Local access to properties shall be maintained at all times.

Weekly Progress

- **Week of June 24th** – Leroy Center Road was closed. Work completed included the installation of erosion control devices, removal of the existing pavement and excavation.
- **Week of July 1st** – Leroy Center Road remains closed. The contractor continued with excavation and grading on site.
- **Week of July 8th** – Leroy Center Road remains closed. The contractor is continued to fill and grade the site as well as began working on the underdrains, storm sewers and ditches. Rain has been a factor this week.
- **Week of July 15th – Anticipated** Vrooman Road will be closed to traffic on Monday. Leroy Center Road will remain closed. Demolition of the pavement on Vrooman Road is expected to begin. Grading, drainage and electrical work are scheduled to be underway as construction on Leroy Center progresses.