



Lake County, Ohio



LAKE COUNTY BUILDING DEPARTMENT

27 WOODLAND ROAD, PAINESVILLE, OHIO 44077

TEL: 440-350-2636 440-918-2636 800-899-LAKE Ext. 2636 FAX: 440-350-2660

www.lakecountyohio.gov/buildinginspection

INSPECTION REQUIREMENTS Page 1 of 5

- **JOB SITE ADDRESS** posted during entire construction process.
- **JOB PLACARD POSTED IN PLAIN SIGHT:**
 - GREEN** Placard - Building, **ORANGE** Placard – Electrical,
 - BLUE** Placard - HVAC, Fire Protection, Demolition, Other
- **APPROVED JOB COPY PLANS MUST BE AVAILABLE ON ALL JOBS FOR ALL INSPECTIONS.** If approved prints are not on the job site, a reinspection must be scheduled – **PLEASE NOTE REINSPECTION FEES.**
- **REINSPECTION FEES** – A Reinspection Fee will be charged when the inspector must return to work that was not ready, building was locked, approved construction documents not on site, and / or had failed a previous inspection. Fee must be paid prior to scheduling final inspection, or if two (2) fees are assessed on a project, fees are due before the next inspection is scheduled.
- **TWENTY-FOUR (24)-HOUR NOTICE** is required for **ALL INSPECTIONS. Inspection Requests must be received by 3:00 p.m. for an inspection the next day.** You can call on the day of your inspection, between 8:00 a.m. – 9:15 a.m. for an approximate inspection time.

.....

• **PLUMBING APPROVALS:** In addition to receiving an inspection approval from the Lake County Building Department, **IT IS THE CONTRACTOR’S / OWNER’S RESPONSIBILITY to obtain all PLUMBING APPROVALS from the Lake County Health District, 33 Mill Street, Painesville, Ohio 44077 Telephone# 440-350-2543.**

.....

1. **FOOTING / PADS / PILINGS INSPECTION:**

- A. Upon completion of Footing Forms, Reinforcement, etc. but **BEFORE INSTALLING CONCRETE** schedule a pre-pour inspection with the Lake County Building Department.
- B. A minimum of **ONE-HOUR** window is required when scheduling for inspection.
- C. Earliest pour time is 10:00 a.m.

2. **FOUNDATION INSPECTION:**

- A. Upon completion of water proofing, drain tile with cover stone in place, and prior to backfilling.



LAKE COUNTY BUILDING DEPARTMENT

27 WOODLAND ROAD, PAINESVILLE, OHIO 44077

TEL: 440-350-2636 440-918-2636 800-899-LAKE Ext. 2636 FAX: 440-350-2660

www.lakecountyohio.gov/buildinginspection

INSPECTION REQUIREMENTS Page 2 of 5

3. SLAB INSPECTION:

- A. Upon completion of insulation, vapor barriers, mesh, etc. but BEFORE INSTALLING CONCRETE schedule a pre-pour inspection with the Lake County Building Department.
 - **Concrete slab and under-floor inspections** shall be made after in-slab or under-floor reinforcing steel and building service equipment, conduit, piping accessories and other ancillary equipment items are in place, but before any concrete is placed or floor sheathing installed, including the subfloor.
- B. A minimum of ONE-HOUR window is required when scheduling for inspection.
- C. Earliest pour time is 10:00 a.m.

D. **PLEASE NOTE:** In addition to receiving an inspection approval from the Lake County Building Department, **IT IS THE CONTRACTOR'S / OWNER'S RESPONSIBILITY to obtain all PLUMBING APPROVALS from the Lake County Health District, 33 Mill Street, Painesville, Ohio 44077 Telephone# 440-350-2543.**

4. STRUCTURE, ELECTRICAL, MECHANICAL, FIRE ALARM, FIRE SPRINKLER ROUGH-IN INSPECTION:

- A. All Additional Permits must be on file (electrical, mechanical, gas piping, etc).
- B. Rough-in inspection approval, in any area, is required before concealment.
- C. Structure, electrical, mechanical roughs, and fireplace shall be inspected at the same time.
 - **Framing:** Complete framing inspections shall be made after the roof deck or sheathing, all framing, fire blocking and bracing are in place and pipes, chimneys and vents to be concealed are complete and the rough electrical, plumbing, heating wires, pipes and ducts are approved. Protection of joints and penetrations in fire-resistance-rated assemblies shall not be concealed from view until inspected and approved.
 - **Electrical:** Complete electrical rough in with all splicing in boxes ready to receive devices.
 - **Mechanical:** Complete mechanical installations including all ductwork, fuel gas piping, equipment, and electrical connections. Heat pipes in concrete slab to be inspected prior to pouring concrete.

D. **PLEASE NOTE:** In addition to receiving an inspection approval from the Lake County Building Department, **IT IS THE CONTRACTOR'S / OWNER'S RESPONSIBILITY to obtain all PLUMBING APPROVALS from the Lake County Health District, 33 Mill Street, Painesville, Ohio 44077 Telephone# 440-350-2543.**



LAKE COUNTY BUILDING DEPARTMENT

27 WOODLAND ROAD, PAINESVILLE, OHIO 44077

TEL: 440-350-2636 440-918-2636 800-899-LAKE Ext. 2636 FAX: 440-350-2660

www.lakecountyohio.gov/buildinginspection

INSPECTION REQUIREMENTS Page 3 of 5

5. **FIREPLACE INSPECTION:**

- A. **Masonry** - to be inspected at top of smoke chamber when first flue tile is set and smoke chamber purged.
- B. **Prefab** - rough in before enclosing. Prefab fireplace inspection should be done at the same time as the structural, electrical, and mechanical rough in inspection.

6. **ENERGY EFFICIENCY – INSULATION INSPECTION:**

- A. After any Rough Plumbing, Rough Framing, Electrical, Mechanical, and any other work that may be concealed has been inspected and approved.
- B. Insulation is completely installed but prior to placement of any drywall or other covering.
- C. Inspections shall include, but not be limited to, inspections for envelope insulation *R* and *U* value, fenestration *U* value, duct system *R* value, and HVAC and water heating equipment efficiency.

D. **PLEASE NOTE:** In addition to receiving an inspection approval from the Lake County Building Department, **IT IS THE CONTRACTOR'S / OWNER'S RESPONSIBILITY to obtain all PLUMBING APPROVALS from the Lake County Health District, 33 Mill Street, Painesville, Ohio 44077 Telephone# 440-350-2543.**

7. **FIRE RESISTANCE RATED CONSTRUCTION INSPECTION:**

- A. Protection of joints and penetrations in fire-resistance-rated assemblies shall not be concealed from view until inspected and approved.
- B. After all wallboard is installed and before wallboard joints and fasteners are taped and finished.

8. **ELECTRICAL SERVICE INSPECTION: (Temporary or Permanent)**

- A. **Temporary Power Pole** - prior to the utility company hook up.
- B. **Permanent Electrical Service** - when main panel is installed and grounding is complete with cover off prior to the utility company hook up.
- C. **Approval** is faxed the next business day to the utility company. The Electrical Contractor / Owner's is responsible for scheduling hook up with the appropriate utility company.



LAKE COUNTY BUILDING DEPARTMENT

27 WOODLAND ROAD, PAINESVILLE, OHIO 44077

TEL: 440-350-2636 440-918-2636 800-899-LAKE Ext. 2636 FAX: 440-350-2660

www.lakecountyohio.gov/buildinginspection

INSPECTION REQUIREMENTS Page 4 of 5

9. REQUESTING A FINAL INSPECTION:

- Upon completion of all phases of any construction. Final inspection approval is required upon completion and approval of all phases of any construction **prior to occupancy**.
- All Fuel Piping Installations must have an **ACCEPTANCE TEST CERTIFICATE** submitted and approved to the Lake County Building Department before a final inspection can be schedule. See Acceptance Test Information in Section 10.
- For Residential New Dwellings – Contact your local jurisdiction’s engineer to request a final grading inspection / approval. If in a township, contact the Lake County Engineer’s Office (550 Blackbrook Rd, Painesville Twp 440-350-2770); otherwise contact your local city or village engineer.

- PLEASE NOTE:** In addition to receiving an inspection approval from the Lake County Building Department, all **PLUMBING APPROVALS** are required from the Lake County General Health District, 33 Mill Street, Painesville, Ohio Tel 440-350-2543. **IT IS THE CONTRACTOR’S / OWNER’S RESPONSIBILITY TO OBTAIN ALL PLUMBING APPROVALS.**

- After submittal and review of all Special Inspection Reports (OBC Section 1704).
- After payment of any reinspection fees.

CONFIRMATION OF APPROVALS REQUIRED TO ISSUE CERTIFICATE OF OCCUPANCY

- Final inspection and approval by the Lake County Building Department.
- Plumbing Certificate of Use issued by the Lake County General Health District, 33 Mill Street, Painesville, Ohio Tel# 440-350-2543.
- Final Grade / Drainage Inspection Request Form from the Lake County Engineer’s Office or the Jurisdiction’s City / Village Engineer Drainage Inspection Form.

CERTIFICATE OF OCCUPANCY COPIES

- Contractors / Owner’s may contact the Lake County Building Department one week after a final inspection has been approved **AND** all confirmations (Final Grade and Plumbing Certificate of Use) are received by the Lake County Building Department, to request a copy of the certificate of occupancy.



LAKE COUNTY BUILDING DEPARTMENT

27 WOODLAND ROAD, PAINESVILLE, OHIO 44077

TEL: 440-350-2636 440-918-2636 800-899-LAKE Ext. 2636 FAX: 440-350-2660

www.lakecountyohio.gov/buildingsinspection

INSPECTION REQUIREMENTS Page 5 of 5

10. ACCEPTANCE TESTS

- A. **Fuel Piping Installations** - prior to acceptance and initial operation shall be inspected and pressure tested to determine that the materials, design, fabrication, and installation practices comply with the requirements of this code.
1. All Fuel Piping Installations must have an **ACCEPTANCE TEST CERTIFICATE** submitted and approved to the Lake County Building Department before a final inspection can be schedule. (OBC 109.9, RCO 108.2.9).
- B. **Automatic Sprinkler Systems**
1. After scheduling tests with the local fire department, notify the Lake County Building Department of the date and time of the test.
 2. Provide Sprinkler Acceptance Test Certificate as required by OBC 901.5 and NFPA 13.
- C. **Fire Alarm Systems** - upon completion of the installation of the alarm notification appliances and circuits, alarm-initiating devices and circuits, supervisory-signal initiating devices and circuits, signaling line circuits, and primary and secondary power supplies shall be tested in accordance with NFPA 72.
1. After scheduling tests with the local fire department, notify the Lake County Building Department of the date and time of the test.
 2. Provide Fire Alarm Acceptance Test Certificate as required by OBC 901.5 and NFPA 72.
- D. **Automatic Fire-Extinguishing System** - including commercial hood and duct systems, commercial cooking systems, dry-chemical systems, foam systems, Halon systems, clean-agent systems, carbon dioxide systems, etc.
1. After scheduling tests with the local fire department, notify the Lake County Building Department of the date and time of the test.
 2. Provide Acceptance Test Certificate as required by OBC 901.5.